

Проектното решение предвижда сградата на центърът за експериментално куклено изкуство да бъде ситуирана западно от сградата на съществуващия куклен театър. Планираната зона за застрояване е добре озеленен двор. Имотът граничи с улици на север и запад и със съществуващо училище на юг. Водещи приоритети при разполагането на новата сграда са запазването на високата растителност и функционалното обвързване със съществуващия театър. Обемно-пространствената композиция е повлияна от изведени градоустройствени репери и линии, както и от очакваното формиране на основни потоци и модели на поведение около и в комплекса. Най-откритата пространствено централна зона от север предпоставя организирането на главния обществен вход. Следва фоайе със смесени функции, което може да бъде обединявано изцяло с прилежаща основна зала и осигурява важни функционални връзки със съществуващата сграда, служебните зони и двора. В непосредствена връзка е и репетиционната зала на втория етаж. В южната част на сградата, на четири етажа, са организирани служебни, административни помещения и резидентен блок. Към тях е обособен самостоятелен вход. Зоната за чакащи артисти е свързана и с двете сцени. Под цялата сграда е предвидено подземно ниво с достъп по рампа от запад, включващо склад за съхранение на инвентар, паркинг и технически помещения. Всички съществуващи и нови складови помещения са обвързани комуникационно. Проектът набляга на интеграцията със съществуващия контекст, създавайки жизнено пространство за артистично изразяване и ангажираност на общността.

Плътност на застрояване: 670 кв. м.

Обща застроена площ: 1400 кв. м.

Обща озеленена площ: 415 кв. м.

Приблизителна стойност за реализация на проекта: 4 000 000 лв.

The Center for Experimental Puppetry is planned to be located west of the existing puppet theater building. The development area is a well landscaped courtyard. The property is adjacent to streets to the north and west and an existing school building to the south. The layout of the new building is prioritized in keeping with the preservation of the existing tree vegetation and functional relation to the old theatre building. The volumetric and spatial composition is influenced by established urban plan benchmarks, as well as the anticipated movement patterns. The most open spatial central area from the north presupposes the organization of the main public entrance. Following is a mixed-use lobby that can be fully integrated with the adjacent main hall. It provides important functional connections to the existing building, service areas and courtyard. The rehearsal room on the second floor is also directly connected. The offices, administrative areas and a residence block are situated on four floors in the southern part of the building. Separate entrance is provided. The performers waiting area is connected to both stages. An underground level accessible by ramp from the west is designed, which includes storage for inventory, parking and technical rooms. All existing and new storage rooms are interconnected. The project emphasizes integration with the existing context creating a vibrant space for artistic expression and community engagement.

Building density: 670 sq. m.

Total built-up area: 1400 sq. m.

Total landscape area: 415 sq. m.

Approximate estimated cost for implementing the project: 4 000 000 BGN.